GARGO HAVEN DEPOT LTD

RTW SHIPPING AND LOGIS

SNo	*Code*	*Item*	*Mat*	*Hr*

CORNER POST (REAR END)

1	PRIN/1	INSERT REAR CORNER POST 30 CM	25.76	2.00
2	PRIN/2	INSERT REAR CORNER POST 30 CM	51.52	4.00
3	PRST/1	STRAIGHTEN REAR CORNER POST 30 CM	5.6	1.25
4	PRWE/1	WELD REAR CORNERN POST 15 CM	0.91	0.50
5	PRSW/2	STRAIGHTEN AND WELD REAR CORNER POST 30 CM	5.04	0.70
6	PRST/2	STRAIGHTEN REAR CORNER POST 60 CM	11.2	2.50
7	PRSW/1	STRAIGHTEN AND WELD REAR CORNER POST 15 CM	2.51	0.35
8	PRWE/2	WELD REAR CORNERN POST 30 CM	1.8	1.00

ACCESSORIES

1	OTTC/1	REPLACE TIR CORD	50	0.00
2	OTTC/2	REPLACE TIR CORD	70	0.00
3	OTRT/2	REPLACE TARPAULIN	560	0.00
4	OTRT/1	REPLACE TARPAULIN	350	0.00
5	OTRG	REPLACE GROMET	5	0.00
6	OTRB/1	REPLACE ROOF BAR	60	0.00
7	OTHP	REPLACE DOOR HEADER PIN	15	0.00
8	FRLP	REPLACE LOCK PIN	0	0.00
9	FRRS	REPLACE SPRING	0	0.00
10	FRTL	REPLACE TWIST LOCK	222	0.00
11	OTTP	PATCH TARPAULIN	60	0.00

APPLYING SEALANT (FLOORBOARDS)

1	MSAFS/3	APPLYING SEALANT ON FLOORBOARDS-120 CM	10	0.75

SNo	Code	Item	Mat	Hr
APPLYING SEALANT (GASKETS)				
1	MSAGS/4	APPLYING SEALANT ON GASKETS -240 CM	7	1.00
APPLYING SEALANT (FLOORBOARDS)				
1	MSAFS/4	APPLYING SEALANT ON FLOORBOARDS-240 CM	12	1.00
APPLYING SEALANT -(FLOORBOARDS)				
1	MSAFS/1	APPLYING SEALANT ON FLOORBOARDS - 30CM	10	0.25
2	MSAFS/2	APPLYING SEALANT ON FLOORBOARDS-60 CM	10	0.50
APPLYING SEALANT (GASKETS)				
1	MSAGS/1	APPLYING SEALANT ON GASKETS -30 CM	5	0.25
APPLYING SEALANT(GASKETS)				
1	MSAGS/3	APPLYING SEALANT ON GASKETS -120 CM	7	0.75
2	MSAGS/2	APPLYING SEALANT ON GASKETS -60 CM	5	0.50
APPY SEALANT				
1	MSAGS	APPLY SEALANT ON GASKET-30 CM	5	0.25
BOTOOM SIDE RAIL				
1	BGSW	STRAIGHTEN AND WELD BOTTOM SIDE RAIL GUSSET (EACH)	1.42	0.50
2	BFWE/1	WELD BOTTOM SIDE RAIL FLANGE FIRST 15 cm	0.91	0.15
3	BRSE/3	SECTION BOTTOM SIDE RAIL (PARTIAL PROFILE) 120 CM	36.45	6.50
BOTTOM				
1	CMRP	REPLACE 1 CROSSMEMBER	60.37	2.25
BOTTOM SIDE RAIL				

SNo	Code	Item	Mat	Hr
1	BFST/3	STRAIGHTEN BOTTOM SIDE RAIL FLANGE 60 CM	3.71	0.50

BOTTOM SIDE RAILS

1	MBWT	STRAIGHTEN BOTTOM SIDE RAIL FLANGE UPTO FISRT 15 CM	0.914	0.15

BOTTOM RAIL

1	BRSE/5	SECTION BOTTOM SIDE RAIL (PARTIAL PROFILE) 480 CM	145.82	24.50
2	BRSE/6	SECTION BOTTOM SIDE RAIL (PARTIAL PROFILE) 960 CM	291.65	46.50
3	BRSE/4	SECTION BOTTOM SIDE RAIL (PARTIAL PROFILE) 240 CM	72.91	12.50

BOTTOM SIDE RAIL

1	BRIF/2	INSERT BOTTOM SIDE TAil (FULL PROFLE) LENGTH 1200 CM	187.94	20.00
2	BRIF/1	INSERT BOTTOM SIDE RAIL (FULL PROFLE) FULL LENGTH 600 CM	93.25	14.00
3	BGRP	REPLACE BOTTOM SIDE RAIL CORNER GUSSET (EACH)	4.83	0.75
4	BRIN/1	INSERT BOTTOM SIDE RAIL (PARTIAL PROFLE() 30 CM	7.514	1.50
5	BRIN/3	INSERT BOTTOM SIDE RAIL (PARTIAL PROFLE) 120 CM	30.07	4.50
6	BRST/3	STRAIGHTEN BOTTOM SIDE RAIL 60 CM	3.65	1.50
7	BRRP/2	REPLACE BOTTOM SIDE RAIL (FULL PROFLE) 1200 CM	350.82	32.00
8	BRRP/1	REPLACE BOTTOM SIDE RAIL (FULL PROFLE) 600 CM	175.4	20.00
9	BRIN/6	INSERT BOTTOM SIDE RAIL (PARTIAL PROFLE) 960 CM	240.64	32.50
10	BRIN/5	INSERT BOTTOM SIDE RAIL (PARTIAL PROFLE) 480 CM	120.31	16.50
11	BRIN/4	INSERT BOTTOM SIDE RAIL (PARTIAL PROFLE) 240 CM	60.15	8.50
12	BRST/7	STRAIGHTEN BOTTOM SIDE RAIL 960 CM	58.22	24.00
13	BRIN/2	INSERT BOTTOT SIDE RAIL (PARTIAL PROFLE) 60 CM	15.03	2.50
14	BRSW/6	STRAIGHTEN AND WELD BOTTOM SIDE RAIL 480 CM	109.71	24.00
15	BRST/1	STRAIGHTEN BOTTOM SIDE RAIL 15CM	0.91	0.50
16	BRST/2	STRAIGHTEN BOTTOM SIDE RAIL 30 CM	1.82	0.75
17	BRSW/1	STRAIGHTEN AND WELD BOTTOM SIDE RAIL FIRST 15CM	3.41	0.75
18	BRSW/2	STRAIGHTEN AND WELD BOTTOM SIDE RAIL 30 CM	6.85	1.25
19	BRSW/3	STRAIGHTEN AND WELD BOTTOM SIDE RAIL60 CM	13.71	3.75

SNo	Code	Item	Mat	Hr
20	BRST/5	STRAIGHTEN BOTTOM SIDE RAIL 240 CM	14.62	6.00
21	BRSW/5	STRAIGHTEN AND WELD BOTTOM SIDE RAIL 240 CM	54.85	12.00
22	BRST/4	STRAIGHTEN BOTTOM SIDE RAIL 120 CM	7.31	3.00
23	BRSW/7	STRAIGHTEN AND WELD BOTTOM SIDE RAIL 960 CM	219.42	48.00
24	RCR	STRAIGHTEN BOTTOM SIDE RAIL FLANGE 30 CM	6.05	0.25
25	BRWE/3	WELD BOTTOM SIDE RAIL 60 M	12.57	1.50
26	BRWE/2	WELD BOTTOM SIDE RAIL 30 CM	6.28	0.75
27	BRST/6	STRAIGHTEN BOTTOM SIDE RAIL 480 CM	29.25	12.00
28	BFWE/3	WELD BOTTOM SIDE RAIL FLANGE 60 cm	3.71	0.60
29	BRSW/4	STRAIGHTEN AND WELD BOTTOM SIDE RAIL 120 CM	27.42	6.00
30	BFST/7	STRAIGHTEN SIDE RAIL FLANGE 960 CM	59.42	5.00
31	BRSE/2	SECTION BOTTOM SIDE RAIL (PARTIAL PROFILE) 60 CM	18.22	3.50
32	BRSE/1	SECTION BOTTOM SIDE RAIL (PARTIAL PROFILE) 30 CM	9.11	2.00
33	BFWE/2	WELD BOTTOM SIDE RAIL FLANGE 30 cm	1.85	0.30
34	BGWE	WELD BOTTOM SIDE RAIL GUSSET (EACH)	0.22	0.25
35	BFST/4	STRAIGHTEN BOTTOM SIDE RAIL FLANGE 120 CM	7.42	0.75
36	BFST/6	STAIGHTEN TOP SIDE RAIL FLANGE 480 CM	29.71	2.50
37	BFSW/1	STRAIGHTEN AND WELD BOTTOM SIDE RAIL FLANGE FIRST 15 CM	1.42	0.25
38	BFSW/2	STRAIGHTEN AND WELD BOTTOM SIDE RAIL FLANGE 30 CM	2.85	0.75
39	BFSW/3	STRAIRHTEN AND WELD BOTTOM SIDE RAIL FLANGE 60 CM	5.714	1.50
40	BFSW/4	STRAIGHTEN AND WELD BOTTOM SIDE RAIL FLANGE 120 CM	11.42	3.00
41	BFSW/5	STRAIGHTEN AND WELD BOTTOM SIDE RAIL FLANGE 240 CM	22.85	6.00
42	BFSW/6	STRAIGHTEN AND WELD BOTTOM SIDE RAIL FLANGE 480 CM	45.714	12.00
43	BFSW/7	STRAIGHTEN AN D WELD BOTTOM SIDE RAIL FLANGE 960 CM	91.42	24.00
44	BFST/5	STRAIGHTEN BOTTOM SIDE RAIL FLANGE 240 CM	14.85	1.00

BOTTOM SIDE RAILS

1	MWCT	STRAIGHTEN BOTTOM SIDE RAIL FLANGE 30CM	1.85	0.25

CHEMICAL CLEANING

SNo	Code	Item	Mat	Hr
1	D10 20'	CHEMICAL WASH 20'	1.13	0.00
2	D10 40'	CHEMICAL WASH 40'	0.72	0.00

CORNER CAST

1	D15	CORNER CAST MISSING / DAMAGED	0.72	0.00

CORNER POST

1	PFRP	REPLACE FRONT CORNER POST COMPLETE WITH COMPONENTS	1132	10.00
2	D13	CORNER POST DAMAGED	1.13	0.00
3	PFIF	INSERT FRONT CORNER POST - PARTIAL PROFILE FULL LENGTH 240 CM	498.08	7.00
4	PFIN/1	INSERT FRONT CORNER POST UPTO FIRST 30 CM	25.76	2.50
5	PFIN/2	INSERT CORNER POST EACH 60CM	51.52	5.00
6	PRPC	REPLACE REAR CORNER POST WITH COMPONENTS	1418.2	14.00
7	CCRP	REPLACE UPPER OR LOWER CORNER FITTING	238.09	3.00

CORNER POST (REAR END)

1	PJSW/2	STRAIGHTEN AND WELD REAR CORNER POSTJ BAR 30 CM	6.05	1.00
2	PJSW/1	STRAIGHTEN AND WELD REAR CORNER POSTJ BAR 15 CM	3.03	0.50
3	PJST/2	STRAIGHTEN REAR CORNER POST J BAR 60 CM	9.52	0.50
4	PJST/1	STRAIGHTEN REAR CORNER POST J BAR 30 CM	4.76	0.25
5	MCPWP	WIRE BRUSH AND PAINT CORNER POST	0.91	1.00

DECALS

1	MDRP/2	REMOVE AND/OR PAINT OVER 15 DIGITS	13.65	3.00
2	MDRP/1	REMOVE AND/OR PAINT 0-15 CUSTOMER DIGITS	2.27	0.15
3	MDRL/2	REPLACE LARGE PYRAMID SIDE LOGO STICKER	48.85	1.50
4	MDRL/1	REPLACE PYRAMID DOOR LOGO STICKER	14.28	0.50
5	MDRDS/1	REPLACE SMALL SINGLE CHARACTER OF WEIGHT PANEL OR FLEET NUMBER	0.47	0.25
6	MDRDS/2	REPLACE MULTIPLES OF SMALL CHARACTERS OF WEIGHT PANEL OR FLEET NUMBER	26.19	2.00

DENTS THAT NEED TO BE STRAINGHTEN

1	D4	13.33 USD PER CORRUGATION	0.72	0.00

DOOR

1	PSRP	REPLACE CSC PLATE	6.73	0.25
2	BSRP	REPLACE SMALL BEARING BRACKET	5.61	0.15
3	D5	LOCK ROD WITH ACCESSORIES MISSING	0.72	0.00

DOOR ASSEBLY

1	HORF	Replace door locking Bar Handle	22.78	0.15

DOOR ASSEMBLY

1	DPST/1	STRAIGHTEN ACCUMULATED DENTS 900 SQURE CM	1.714	0.50
2	DPNH	REPLACE ONE DOOR PANEL 120X240 CM WITH NEW HARDWARE	215.56	12.00
3	DPIN/5	PACH DOOR PANEL 14400 SQYRE CM	10.28	2.50
4	DPIN/4	PACH DOOR PANEL 7200 SQURE CM	48	2.00
5	DPIN/3	PACH DOOR PANEL 3600 SQURE CM	24	1.50
6	DHPA	PACH DOOR PANEL BEHIND HINGE	14.23	1.75
7	DHIN	INSERT DOOR PANEL BEHIND HINGE	14.23	1.75
8	DEIN	INSERT UPPER OR LOWER FACE DOOR PANEL EDGE 120X20 CM INCLUDING REMOVEL/REINSTALL HARDWARE	19.93	4.00
9	DPWE/2	WELD DOOR PANEL PIN HOLES - EACH SET OF 6 AND ABOVE HOLES OR 30 CM	1.82	1.00
10	DEPA	PATCH UPPER OR LOWER FACE DOOR PANEL EDGE 120X20 CM INCLUDING REMOVAL/REINSTALL HARDWARE	19.93	4.00
11	HBST	STRAIGHTEN HINGE BLADE	1.7	0.25
12	HCRP	Replace Door Handle Catch Only	3.13	0.25
13	HDSE/1	SECTION DOOR HEADER - FULL PROFILE UPTO FIRST 30 CM	7.4	2.00
14	HDIF	INSERT DOOR HEADER -PARTIAL PROFILE FULL LENGTH 240 CM	36.44	6.00
15	HDIN/1	INSERT DOOR HEADER - PARTIAL PROFILE UPTO FIRST 30 CM	6.26	1.25
16	HLRP	REPLACE HINGE LUG AND PIN	22.78	0.75
17	HPRP	REPLACE HINGE PIN ONLY	14.23	0.25

SNo	Code	Item	Mat	Hr
18	DSSW/1	STRAIGHTEN & WELD 15 CM OF DOOR EDGE FRAME	0.91	1.20
19	DPIN/1	PATCH DOOR UPTO 225 SQ CM (15*15 CM)	1.5	0.75
20	DPWE/1	WELD DOOR PANEL PIN HOLES 1-6 HOLES OR 15 CM	0.91	0.50
21	DPSW/2	STRAIGHTEN AND WELD DOOR PANEL CUT 30 CM	1.82	1.00
22	DPSW/1	STRAIGHTEN AND WELD DOOR PANEL CUT UPTO 15 CM	0.91	0.50
23	DPST/6	STRAIGHTEN ACCUMULATED DENTS 28800 SQ CM (120*240)	54.85	6.00
24	DPST/5	STRAIGHTEN ACCUMULATED DENTS 14400 SQ CM (120*120CM)	27.42	5.15
25	DPST/4	STRAIGHTEN ACCUMULATED DENTS 7200 SQ CM (60*120 CM)	13.71	2.75
26	DPST/3	STRAIGHTEN ACCUMULATED DENTS 3600 SQ CM (60*60 CM)	6.85	2.15
27	DPIN/2	PATCH DOOR PANEL 900 SQ (30*30 CM)	6	1.00
28	DSSW/2	STRAIGHTEN & WELD 30 DOOR EDGE FRAME	1.82	2.40
29	PLRS	STRAIGHTEN AND RESECURE STAINLESS STEEL CARGO LABEL PLATE	4.48	0.10
30	DARP	REPLACE ONE DOOR ASSEMBLY COMPLETE USING EXISTING HARDWARE	129.84	8.00
31	PLRM	REMOVE AND REINSTALL CARGO LABEL PLATE	1.68	0.25
32	PLRP	REPLACE STAINLESS CARGO LABEL PLATE	8.68	0.25

DOOR FRAME

1	D18	HEADER, FRONTOR DOOR DAMGED	0.72	0.00

DOOR HANDLE

1	HCFU	FREE-UP DOOR LOCKING BAR CATCH	0.91	0.10

DOOR HANDLE ASSEMBLY

1	HHRP	REPLACE DOOR LOCKING BAR HANDLE HUB	4.55	0.50
2	HHST	STRAIGHTEN DOOR LOCKING BAR HANDLE HUB	0.91	0.15
3	HOFU	FREE-UP DOOR LOCKING BAR HANDLE	0.91	0.10
4	HORP	REPLACE DOOR LOCKING BAR HANDLE HUB	22.78	0.15
5	HRRP	REPLACE DOOR LOCKING BAR HANDLE RETAINER ONLY	4.55	0.15
6	LARP	REPLACE COMPLETE DOOR LOCKING BAR ASSEMBLY	112.76	0.15
7	HKRP	REPLACE DOOR LOCKING BAR RETAINER AND CATCH	10.24	0.25

SNo	Code	Item	Mat	Hr
8	HKST	STRAIGHTEN DOOR HANDLE RETAINER AND CATCH	0.91	0.15
9	HOST	STRAIGHTEN DOOR LOCKING BAR HANDLE	0.91	0.25
10	HKRM	REMOVE AND REINSTALL LOCKING BAR RETAINER CATCH	1.7	0.15
11	HCST	STRAIGHTEN LOCKING BAR CATCH	0.91	0.05
12	HRST	STRAIGHTEN DOOR LOCKING BAR HANDLE RETAINER ONLY	0.91	0.05

DOOR HEADER (REAR TOP RAIL)

1	HGRP	REPLACE DOOR HEADER INTERIOR GUSSET(EACH)	4.83	0.25
2	HDST/2	STRAIGHTEN DOOR HEADER 30 CM	1.82	1.00
3	HDIN/2	INSERT DOOR HEADER (PARTIAL PROFILE) 60 CM	12.53	2.50
4	HDRP	REPLACE 240 CM DOOR HEADER (FULL PROFILE) COMPLETE WITH COMPONENTS	113.9	13.00
5	HDSE/2	SECTION DOOR HEADER (FULL PROFILE) 60 CM	14.8	4.00
6	HDST/1	STRAIGHTEN DOOR HEADER 15 CM	0.91	0.50
7	HDSW/2	STRAIGHTEN AND WELD DOOR HEADER 30 CM	1.82	1.20
8	HDWE/2	WELD EACH ADDITIONAL 15 CM ON DOOR HEADER	1.82	1.00
9	HGSW	STRAIGHTEN AND WELD DOOR HEADER INTERIOR GUSSET (EACH)	0.91	0.15
10	HDSW/1	STRAIGHTEN AND WELD DOOR HEADER 15 CM	0.91	0.60
11	HDWE/1	WELD 15 CM ON DOOR HEADER	0.91	0.50

DOOR HINGE ASSEMBLY

1	HARP	REPLACE COMPLETE DOOR HINGE ASSEMBLY (BLADE,LUG AND PIN)	34.17	1.50
2	FAHU	FREE UP 4 WINGES (PER DOOR)	3.13	0.50
3	HBRP	REPLACE HINGE BLADE ONLY	9.11	1.25

DOOR LOCKING BAR ASSEMBLY

1	LBRP	REPLACE DOOR LOCKING BAR ONLY	44.77	1.50
2	BLRM	REMOVE AND REINSTALL LARGE BEARING BRACKET	3.99	0.25
3	BLRP	REPLACE END BEARING BRACKET (LARGE)	7.4	0.25
4	BSST	STRAIGHTEN SMALL BEARING BRACKET	0.91	0.10
5	BLRS	RESECURE LARGE BEARING BRACKET	0.91	0.25

SNo	Code	Item	Mat	Hr
6	BSRS	RESECURE SMALL BEARING BRACKET	0.91	0.15
7	BSRM	REMOVE AND RAINSTALL SMALL BEARING BRACKET	0.91	0.15
8	LBSE/1	SECTION DOOR LOCKING BAR 30 CM	5.69	0.75
9	LBFU	FREE UP DOOR LOCKING BAR (EACH)	2.79	0.10
10	BLST	STRAIGHTEN LARGE BEARING BRACKET	0.91	0.25
11	LCRP	REPLACE DOOR LOCKING CAM ONLY	51.25	2.50
12	LBSE/2	SECTION DOOR LOCKING BAR 60 CM	11.39	1.50
13	LBST	STRAIGHTEN DOOR LOCKING BAR	3.13	0.50
14	LKRP	REPLACE DOOR LOCKING BAR CAM RETAINER (KEEPER) ONLY	51.25	2.50
15	LKRS	RESECURE DOOR LOCKING BAR CAM KEEPER	3.13	0.25
16	HRRPR	REPLACE DOOR LOCKING BAR HANDLE RETAINER ONLY	0	0.15

DOOR PANEL.

1	GSSE/1	SECTION 120 CM DOOR GASKET RETAINER STRIP	1.7	0.35
2	GSST/1	STRAIGHTEN AND FASTEN 120 CM DOOR GASKET RETAINER STRIP	0.91	0.25

DOOR SEAL AND RETAINING STRIP

1	GDSE/1	SECTION DOOR SEAL UPTO FIRST 120 CM INCLUDING STRIP AND CONER TABS	15.94	0.75
2	GDSE/2	SECTION DOOR SEAL ADDITIONAL 240 CM INCLUDING STRIP AND CORNER TABS	31.88	1.50
3	GSRP	REPLACE COMPLETE DOOR GASKET RETAINER STRIP 720 CM	8.82	2.00
4	GSSE/2	SECTION 240 CM DOOR GASKET RETAINER STRIP	3.4	0.75
5	GSST/2	STRAIGHTEN AND FASTEN EACH ADDITIONAL 240 CM DOOR GASKET RETAINER STRIP	1.82	0.50
6	GDRP	REPLACE COMPLETE DOOR SEAL (INCLUDING RETAINING STRIP) 720 CM	93.97	3.00

DOOR SILL

1	DSIN/2	INSERT DOOR SILL (PARTIAL PROFILE) 60 CM	20.72	3.00
2	DSIN/1	INSERT DOOR SILL (PARTIAL PROFILE) 30CM	10.36	1.50
3	DSSE/1	SECTION DOOR SILL(FULL PROFILE)30CM	11.84	2.00
4	DSSE/2	SECTION DOOR SILL(FULL PROFILE) 60CM	23.69	4.00
5	D16	DOOR SILL DAMAGED	0.72	0.00

SNo	Code	Item	Mat	Hr

DOOR SILL (REARE BOTTOM RAIL)

1	DSWE/2	WELD DOOR SILL 30 CM	1.82	1.00
2	DSWE/1	WELD DOOR SILL 15 CM	0.91	0.59
3	DSST/2	STRAIGHTEN DOOR SILL 30 CM	1.82	1.00
4	DSST/1	STRAIGHTEN DOOR SILL 15 CM	0.91	0.50
5	DSRP	REPLACE 240 CM DOOR SILL RAIL (FULL PROFILE) COMPLITE WITH COMPONENT AND EXISTING KEEPERS	113.9	13.00
6	DSIF	INSERT DOOR SILL (PARTIAL PROFILE) FULL LEINGHT 240 CM	77.74	4.50

DOOR SILL (REAR BOTTOM RAIL)

1	DFWE/1	WELD DOOR SILL BOTTOM FLANGE 15 CM	1.18	0.15

DOOR STILL (REAR BOTTOM RAIL)

1	DFSW/1	STRAIGHTEN AND WELD DOOR SILL BOTTOM FLANGE 15 CM	1.18	0.25
2	DGRP	REPLACE DOOR SILL INTERIOR GUSSET (EACH)	1.18	0.50
3	DFSW/2	STRAIGHTEN AND WELD DOOR SILL BOTTOM FLANGE 30 CM	2.36	0.50
4	DFST/2	STRAIGHTEN DOO SILL BOTTOM FLANGE 30 CM	2.36	0.30
5	DFST/1	STRAIGHTEN DOO SILL BOTTOM FLANGE 15 CM	1.18	0.15
6	DGSW	STRAIGHTEN AND WELD DOOR SILL INTERIOR GUSSET (EACH)	5.714	0.20
7	DFWE/2	WELD DOOR SILL BOTTOM FLANGE 30 CM	2.36	0.30

DOORS

1	D6	ONE SIDE MISSING/ TO REPLACE	1.13	0.00

END RAIL (FRONT TOP RAIL)

1	ERSW/1	STRAIGHTEN AND WELD 15 CM OF FRONT TOP RAIL	0.91	0.50
2	ERST/2	STRAIGHTEN FRONT TOP RAIL 30 CM	1.82	1.00
3	ERST/1	STRAIGHTEN FRONT TOP RAIL 15 CM	0.91	0.50
4	ERRP	REPLACE 240 CM FRONT TOP RAIL (FULL PROFILE) COMPLETE WITH COPONENT	56.95	6.50
5	ERIN/3	INSERT FRONT TOP RAIL (PARTIAL PROFILE) 120 CM	32.78	4.00

SNo	Code	Item	Mat	Hr
6	ERIN/2	INSERT FRONT TOP RAIL (PARTIAL PROFILE) 60 CM	11.39	2.00
7	ERIF	INSERT FRONT TOP RAIL (PARTIAL PROFILE) 240 CM	34.17	5.00
8	EGRP	REPLACE FRONT TOP RAIL INTERIOR GUSSET (EACH)	4.78	0.50
9	ERIN/1	INSERT FRONT TOP RAIL (PARTIAL PROFILE) 30 CM	5.69	1.00
10	ERSW/2	STRAIGHTEN AND WELD 30 CM OF FRONT TOP RAIL	1.82	1.00
11	EGSW	STRAIGHTEN AND WELD FRONT TOP RAIL INTERIOR GUSSET (EACH)	0.91	0.25

END RAIL(FRONT TOP RAIL)

1	ERSE/2	SECTION FRON TOP RAIL 60 CM	17.65	3.00
2	ERWE/2	WELD 30 CM END TOP RAIL	2.85	0.50
3	ERWE/1	WELD 15 CM OF END TOP RAIL	1.42	0.25
4	ERSE/1	SECTION FRONT TOP RAIL 30 CM	8.82	1.50

ENTIRE EXTERIOR

1	EECW20	20FT COLD WASH ENTIRE EXTERIOR	15	0.00

ENTIRE EXTERIOR ALL PANELS

1	EECW40	COLD WASH 40FT ENTIRE EXTERIOR PANELS	25	0.00

ENTIRE INTERIOR COLD WASH

1	EICW40	40FT COLD WASH ENTIRE INTERIOR	20	0.00

ENTIRE INTERIOR CONTAINER

1	EICW20	20FTCOLD WASH:FLOORBOARD,WALL PANELS AND ROOF	10	0.00

FLOOR

1	CHM40	FLOOR WITH UNKNOWN SUBSTANCE CHEMICAL WASH -40FT	2000	0.00
2	CLD40	FLOOR DIRTY COLD WASH -40	375	0.00
3	D8	PLYWOOD BOARD MISSING/DAMAGED 120 X 240	1.13	0.00
4	CHM20	FLOOR WITH UNKNOWN SUBSTANCE CHEMICAL WASH -20FT	1000	0.00

SNo	Code	Item	Mat	Hr
5	D11 20'	REMOVING DEBRIS	0.72	0.00
6	STM20	FLOOR WITH OIL STAINED STEAM CLEAN	375	0.00
7	D7	PLYWOOD BOARD MISSING/DAMAGED 120 X 120	1.13	0.00
8	D11 40'	REMOVING DEBRIS	0.72	0.00

FLOOR ASSEMBLY (PLYWOOD SHEETS)

1	FYRP	Section floor Plywood 3600 sq cm	28.3	1.00

FLOOR ASSEMBLY (LAMINATED HARDWOOD)

1	FLSE/3	SECTION FLOOR LAMINATED PLYWOOD - 28800 SQURE CM	285.25	6.00
2	FLSE/1	SECTION FLOOR LAMINATED PLYWOOD - 7200 SQURE CM	71.31	2.00
3	FLRP/2	REPLACE 1200X240 CM LAMINATED PLYWOOD FLOOR COMPLATE	2614.9	60.00
4	FLCL/1	GRIND (SAND) CLEAN LAMINATED FLOOR 600X240 CM	48.42	8.00
5	FLCL/2	GRIND (SAND) CLEAN LAMINATED FLOOR 1200X240 CM	96.85	16.00
6	FLRP/1	REPLACE 600X240 CM LAMINATED PLYWOOD FLOOR COMPLETE	1307.4	30.00

FLOOR ASSEMBLY (MISC)

1	FDRM/1	REMOVE CARCO DEBRIS 600X240 CM	11.9	1.00
2	FDRM/2	REMOVE CARCO DEBRIS 1200X240 CM	23.8	2.00

FLOOR ASSEMBLY (SOLID PLANK BOARD)

1	FBSE/1	SECTION FLOOR PLANK MINIMUM 15 CM	2.22	1.25
2	FBSE/3	SECTION EACH ADDITIONAL FLOOR PLANK PER LINER 60 CM	6.68	1.75
3	FBSE/7	SECTION EACH ADDITIONAL FLOOR PLANK PER LINER 240 CM	17.82	3.50
4	FBSE/4	SECTION EACH ADDITIONAL FLOOR PLANK PER LINER 90 CM	8.91	2.00
5	FBSE/5	SECTION EACH ADDITIONAL FLOOR PLANK PER LINER 120 CM	11.14	2.25
6	FBSE/6	SECTION EACH ADDITIONAL FLOOR PLANK PER LINER 180 CM	15.6	3.00
7	FBSE/2	SECTION EACH ADDITIONAL FLOOR PLANK PER LINER 30 CM	4.45	1.50

FLOOR ASSEMBLY (HARDWOOD)

SNo	Code	Item	Mat	Hr
1	FLRS	RESECUR FLOORBOARD WITH SCREW	0.34	0.15

FLOOR ASSEMBLY (MISC)

1	FCST/2	STRAIGHTEN CENTER SPACER 30 CM	0	0.30
2	FNRM/2	REMOVE NAILS / FILL HOLES MORE THAN 10 HOLES	19.04	4.00
3	FTRP	REPLACE THRESHOLD PLATE -14400 SQ CM	41.14	6.00
4	FTST	STRAIGHTEN THRESHOLD PLATE	0.91	0.15
5	FTRS	RESECURE THRESHOLD PLATE EACH SCREW	0.34	0.00
6	FNRM/1	REMOVE NAILS/FILL HOLES UPTO 10	14.28	3.00
7	FCST/1	STRAIGHTEN CENTER SPACER 15 CM	47.28	0.15

FLOOR ASSEMBLY (PLYWOOD SHEETS)

1	FYRS	RESECURE UPTP 1 FLOOR SCREW	0.34	0.00
2	FYCL/1	GRIND (SAND) CLEAN PLYWOOD FLOOR 600X240 CM	48.42	8.00
3	FYRP/1	SECTION FLOOR PLYWOOD 7200 SQ CM	54.85	2.00
4	FYRP/2	Section floor plywood 14400 sq cm	108.67	4.00
5	FYCL/2	GRIND (SAND) CLEAN PLYWOOD FLOOR 1200X240 CM	96.85	16.00

FLOOR ASSEMBLY (SOLD PLANK)

1	FPRP/1	REPLACE 600X240 PLANK BOARD FLOOR COMPLETE	253.56	16.00

FLOOR ASSEMBLY (SOLID PLANK)

1	FPRP/2	REPLACE 120*240 CM -PLANKBOARD FLOOR COMPLETE	507.12	6.00
2	FLSE/2	SECTION FLOOR PLYWOOD-14400sq CM	142.62	4.00
3	FYRP/3	SECTION FLOOR PLYWOOD-28800 sq CM	219.42	6.00

FLOOR ASSEMBLY(SOLID PLANK)

1	FPCL/1	GRIND (SAND) CLEAN PLANK FLOOR 600*240 CM	48.42	8.00
2	FPCL/2	GRIND (SAND) CLEAN PLANK FLOOR 1200*240 CM	96.85	16.00
3	FPRS	RESECURE FLOORBOARD WITH SCREW	0.34	0.50

SNo	Code	Item	Mat	Hr
FLOOR CLEANING				
1	D9 40'	COLD WASH 40'	1.13	0.00
2	D9 20'	COLD WASH 20'	1.13	0.00
FLOOR DIRTY COLD WASH				
1	CLD20	FLOOR DIRTY COLD WASH-20FT	375	0.00
FLOOR GRINDING				
1	MFGPS	FLOOR GRANDING -28800 SQURE CM	5.61	1.00
FORK POCKET ASSEMBLY				
1	FSRP	REPLACE FORK POCKET STRAP (ONLY)	6.83	0.75
2	FAIF	INSERT FORK POCKET SIDE FULL LENGHT 240 CM	52.68	2.50
3	FSSW	STRAIGHTEN AND WELD FORK POCKET STRAP (ONLY)	0.91	0.50
4	FSWE	WELD (ONLY) FORK POCKET STRAP	41.14	0.25
5	FAWE/1	WELD FORK POCKET SIDE 15 CM	0.91	0.25
6	FXST	STRAIGHTEN BOTTOM FLANGE FORK POCKETS	0.91	0.25
7	FARP	REPLACE FORK POCKET ASSEMBLY COMPLETE WITH STRAPS AND TOP PLATE	218.69	6.50
8	FSST	STRAIGHTEN FORK POCKET STRAP (ONLY)	0.91	0.25
9	FAIN/1	INSERT FORK POCKET UP TO 30 CM	7.28	1.00
10	FASW/2	STRAIGHTEN AND WELD FORK POCKET SIDE 30 CM	1.82	1.00
11	FAIN/2	INSERT FORK POCKET UP TO 60 CM	14.57	2.00
12	FASW/1	STRAIGHTEN AND WELD FORK POCKET SIDE 15 CM	0.91	0.50
13	FAST	STRAIGHTEN FORK POCKET SIDE	0.91	0.75
14	FAWE/2	WELD FORK POCKET SIDE 30 CM	1.82	0.50
FRONT BOTTOM RAIL				
1	FFST/2	STRAIGHTEN FRONT BOTTOM RAIL FLANGE 30 CM	1.82	0.30
2	FGSW	STRAIGHTEN AND WELD FRONT BOTTOM RAIL INTERIOR GUSSET (EACH)	0.91	0.15

SNo	Code	Item	Mat	Hr
3	FRWE/2	WELD FRONT BOTTOM RAIL 30 CM	1.82	0.50
4	FRST/1	STRAIGHTEN FRONT BOTTOM RAIL 15 CM	0.91	0.50
5	FRIN/1	INSERT FRONT BOTTOM RAIL (PARTIAL PROFILE) 30 CM	7.97	1.25
6	FRIN/2	INSERT FRONT BOTTOM RAIL (PARTIAL PROFILE) 60 CM	15.94	2.50
7	FRIF	INSERT FRONT BOTTOM RAIL (PARTIAL PROFILE) FULL LENGTH 240 CM	63.77	10.00
8	FRGP	REPLACE FRINT BOTTOM RAIL INTERIOR GUSSET (EACH)	4.83	0.25
9	FRIN/3	INSERT FRONT BOTTOM RAIL (PARTIAL PROFILE) 120CM	31.88	5.00
10	FFWE/1	WELD FRONT BOTTOM RAIL FLANGE 15 CM	0.91	0.25
11	FST/2	STRAIGHTEN FRONT BOTTOM RAIL FLANGE 30 CM	0.91	1.00
12	FFWE/2	WELD FRONT BOTTOM RAIL FLANGE 30 CM	1.82	0.50
13	FFSW/1	STRAIGHTEN AND WELD FRONT BOTTOM RAIL FLANGE 15 CM	0.91	0.25
14	FRST/2	STRAIGHTEN FRONT BOTTOM RAIL 30 CM	1.82	1.00
15	FRSW/1	STRAIGHTEN AND WELD FRONT BOTTOM RAIL 15 CM	0.81	0.75
16	FRSW/2	STRAIGHTEN AND WELD FRONT BOTTOM RAIL 30 CM	1.82	1.50
17	FRSW/3	STRAIGHTEN AND WELD FRONT BOTTOM RAIL 60 CM	3.65	3.00
18	FRWE/1	WELD FRONT BOTTOM RAIL 15 CM	0.91	0.25
19	FRRP	REPLACE 240 cm FRONT BOTTOM RAIL(FULL PROFILE) COMPLETE WITH COMPONENTS	113.9	6.50
20	FFSW/2	STRAIGHTEN AND WELD FRONT BOTTOM RAIL FLANGE 30 CM	1.82	0.50

FRONT BOTTON RAIL

1	FFST/1	STRAIGHTEN FRONT BOTTOM RAIL FLANGE 15 CM	0.91	0.15

FRONT CONNER POST

1	PFWE/2	WELD FRONT CORNER POST 30 CM	6.73	1.00
2	PFWE//1	WELD FRONT CORNER POST 15 CM	3.37	0.50
3	PFSW/1	STRAIGHTEN AND WELD FRONT CORNER POST 15 CM	3.37	1.00
4	PFST/2	STRAIGHTEN FRONT CORNER POST 60 CM	12.33	3.00
5	PFST/1	STRAIGHTEN FRONT CORNER POST 30 CM	6.17	1.50
6	PFSW/2	STRAIGHTEN AND WELD FRONT CORNER POST 30 CM	6.73	2.00

SNo	Code	Item	Mat	Hr

FRONT PANEL

1	FPPA/3	PATCH FRONT PANEL 3600 SQ CM	20.57	1.50
2	FPPA/4	PATCH FRONT PANEL 7200 SQ CM	41.14	2.00
3	FPPA/5	PATCH FRONT PANEL 14400 SQ CM	82.28	2.50
4	FPPA/6	REPLACE ONE FRONT PANEL 120X240 CM	164.57	6.00

FRONT SIDE PANELS

1	FPST/4	STRAIGHTEN ACCUMULATED DENTS 7200 SQ CM (60*120CM)	13.71	2.75
2	FPWE/1	WELD FRONT PANEL 15 CM CUT OR 1-6 PIN HOLES	0.91	0.50
3	FPSW/2	STRAIGHTEN AND WELD FRONT PANEL 30 CM	1.82	1.00
4	FPSW/1	STRAIGHTEN AND WELD FRONT PANEL 15 CM	0.91	0.50
5	FPST/5	STRAIGHTEN ACCUMULATED DENTS 14400 SQ CM (120*120 CM)	27.42	5.15
6	FPWE/2	WELD FRONT PANEL 30 CM CUT (OR 6 PIN HOLES & ABOVE)	1.82	1.00
7	FPST/3	STRAIGHTEN ACCUMULATED DENTS 3600 SQ CM (60*60CM)	6.85	2.15
8	FPST/2	STRAIGHTEN ACCUMULATED DENTS 1800 SQ CM (30*60 CM)	3.42	1.00
9	FPST/1	STRAIGHTEN ACCUMULATED DENTS 900 SQ CM (30*30 CM)	1.714	0.50
10	FPPA/2	PATCH FRONT PANEL 900 SQ CM (30*30CM)	5.14	1.00
11	FPPA/1	PATCH FRONT UPTO 225 SQ CM (15*15CM)	1.28	0.75
12	FPST/6	STRAIGHTEN ACCUMULATED DENTS 28800 SQ CM (120*240 CM)	54.85	6.00

GENERAL

1	CW40	COLD WASH 40 FEET	9	0.00
2	MGMCC/20	CHEMICAL CLEAN ENTIRE INTERIOR 600CM	144.55	4.00
3	FYSC	STEAM CLEAN PLYWOOD FLOOR	0	0.75
4	NULL/1	RETURNED UNIT	0	0.00
5	STM40	STEAM CLEAN 40 FEET	375	0.00
6	MCCF	CHEMICAL WASH 40 FEET	100	0.00
7	MGMCC/40	CHEMICAL CLEAN ENTIRE INTERIOR 1200CM	187.91	6.00
8	CW20	COLD WASH 20 FEET	4.5	0.00

SNo	Code	Item	Mat	Hr
9	MCCT	CHEMICAL WASH 20 FEET	80	0.00

GENERAL MAINTENANCE

1	MSWI	SEA WORTHY INSPECTION	0	0.00
2	MGMCC/2	CHEMICAL CLEAN ENTIRE INTERIOR 1200 CM CONTAINER	193.38	6.00
3	MGMSC/1	STEAM CLEAN ENTIRE INTERIOR 600 CM CONTAINER	36.48	1.00
4	MGMSC/2	STEAM CLEAN ENTIRE INTERIOR 1200 CM CONTAINER	51.02	4.00
5	MGMWW/1	WATER WASH ENTIRE INTERIOR 600 CM CONTAINER	16.82	1.00
6	MGMCC/1	CHEMICAL CLEAN ENTIRE INTERIOR 600 CM CONTAINER	148.75	4.00
7	MCWF	COLD WASH FLOOR 40 FEET	45	0.00
8	MGMWW/2	WATER WASH ENTIRE INTERIOR 1200 CM CONTAINER	23.55	2.00
9	MCWT	COLD WASH FLOOR 20 FEET	25	0.00
10	MSCT	STEAM CLEAN FLOOR 20 FT	15	0.00
11	MNAP	NEUTRALIZE TO ALMAR PREFIX	0	0.00
12	MFBLT	LINNING OF FLOOR 144000 SQ CM WITH 3 MM PYLWOOD	47.3	3.00
13	MFBLS	LINNING OF FLOOR 28800 SQ CM WITH 3 MM PYLWOOD	9.47	1.00
14	MSCF	STEAM CLEAN FLOOR 40 FT	30	0.00
15	MFBLF	LINNING OF FLOOR 288000 SQ CM WITH 3 MM PYLWOOD	94.78	6.00

GOOSE NECK

1	TLRP	REPLACE 315 CM GOOSENECK TUNNEL LONGITUDINAL RAIL	193.16	7.00

INTERIOR PANELS

1	D12 40'	INTERIOR REFURBISHMENT/ WIRE BRUSH	17.4	0.00
2	D12 20'	INTERIOR REFURBISHMENT/ WIRE BRUSH	8.7	0.00

J ABR

1	PJWE/1	WELD REAR CORNER J BAR 15 CM	0.91	0.25

J BAR

SNo	Code	Item	Mat	Hr
1	PJWE/2	WELD REAR CORNER J BAR 30 CM	1.8	0.50
2	PJIN/2	INSERT REAR CORNER POST J BAR 60 CM	19.05	1.50
3	PJIN/1	INSERT REAR CORNER POST J BAR 30 CM	9.53	0.75

LASHING RINGS

1	MCLS	STRAIGHTEN CARGO LASHING RINGS (EACH)	0.91	0.10
2	MCLSW	STRAIGHTEN AND WELD CARGO LASHING RINGS (EACH)	0.91	0.25
3	MCLW	WELD ONLY CARGO LASHING RINGS (EACH)	0.91	0.15
4	MCLR	REPLACE CARGO LASHING RINGS (EACH)	0.91	0.25

PAINTING INTERIOR

1	MWBPP/40	WIRE BRUSH,PRIME & PAINT ENTIRE INTERIOR	90.91	0.00

PANEL

1	MWBTP/20	WIRE BRUSH AND TOUCH PAINT ENTIRE INTERIOR	13.64	0.00
2	MWBPP\40	WIRE BRUSH,PRIME & PAINT ENTIRE INTERIOR	90.91	0.00
3	MWBPP/20	WIRE BRUSH,PRIME & PAINT ENTIRE INTERIOR	0	0.00
4	MWBTP/40	WIRE BRUSH AND TOUCH PAINT ENTIRE INTERIOR	27.27	0.00

PANELS(FRONT,SIDE,ROOF)

1	D1	CRACKS/HOLES IN PANELS:60X60 (CM)	3.55	0.00
2	D2	CRACKS/HOLES IN PANELS:120X120 (CM)	0.72	0.00
3	D3	CRACKS/HOLES IN PANELS:240X120 (CM)	0.72	0.00

PIL

1	OT001	20' TARPAULIN MISSING/TORN BEYOND REPAIR REPLACE	36500	0.45

PLATE

1	PRCD	REPLACE CONSOLIDATED DATA PLATE	6.73	0.50
2	PSRS	STRAIGHTEN AND RESECURE CSC PLATE	0.79	0.10

SNo	Code	Item	Mat	Hr
PLATES				
1	PDRP	STAINGTEN AND RESECURE CERTIFICATE TREATMENT PLATE TIR	3.03	0.10
2	PCRP	REPLACE CERTIFICATE PLATE TIR	71.67	0.25
3	PARS	STAINGTEN AND RESECURE AUSTRALIAN WOOD TREATMENT PLATE	3.07	0.10
4	PARP	REPLACE AUSTRALIAN WOOD TREATMENT PLATE	6.73	0.15
RAIL				
1	FRSE/1	SECTION FRONT BOTTOM RAIL(FULL PROFILE) 15CM	4.83	0.75
2	FRSE/2	SECTION FRONT BOTTOM RAIL(FULL PROFILE) 30CM	9.68	2.00
RAILS				
1	D17	TOP OR BOTTOM RAIL DAMAGED 60 CM	0.72	0.00
RAIN GUTTER				
1	GSSW	STRAIGMTEN AND WELD RAIN GUTTER	0.91	0.25
2	GSRT	STRAIGHTEN RAIN GUTTER	0.91	0.10
3	GRWE	WELD RAIN GUTTER	0.91	0.25
4	GRRM	REMOVE RAIN GUTTER	3.07	0.75
REAR CORNER POST				
1	PRRP	REPLACE REAR CORNER POST COMPLETE WITH COMPONENTS	1460.6	14.00
ROOF				
1	RPRP	REPLACE FLAT ROOF PANEL 120X120 CM	107.87	6.00
2	RCRP/1	REPLACE CORRUGATED ROOF PANEL 120 X 120 CM	156.78	4.50
3	RPPA/4	PATCH FLAT ROOF PANEL 7200sq CM	40.45	2.00
4	RCST/4	STRAIGHTEN ACCUMILATED DENTS 7200 SQ CM	11.34	2.75
5	RPPA/5	PATCH FLAT ROOF PANEL14400sq CM	80.9	2.50

SNo	Code	Item	Mat	Hr

ROOF ASSEMBLY (FLAT)

1	RPST/1	STRAIGHTEN ACCUMILATED DENTS 900 SQ CM	3.38	0.50
2	RPST/6	STRAIGHTEN ACCUMILATED DENTS 28800 SQ CM	53.94	12.00
3	RPPA/1	PATCH FLAT ROOF PANEL 225 SQURE CM	1.27	0.75
4	RPPA/2	PATCH FLAT ROOF PANEL 900 SQURE CM	5.06	1.00
5	RPPA/3	PATCH FLAT ROOF PANEL 3600 SQURE CM	20.5	1.50
6	RPST/2	STRAIGHTEN ACCUMILATED DENTS 1800 SQ CM	6.75	1.00
7	RPST/3	STRAIGHTEN ACCUMILATED DENTS 3600 SQ CM	13.49	2.00
8	RPST/5	STRAIGHTEN ACCUMILATED DENTS 14400 SQ CM	40.45	6.00
9	RPSW/1	STRAIGHTEN AND WELD FLAT ROOF PANEL 15 CM	0.91	0.50
10	RPSW/2	STRAIGHTEN AND WELD FLAT ROOF PANEL 30 CM	18.03	1.00
11	RPWE/1	WELD ROOF PANEL PIN HOLES - 1 - 6 PIN HOLES OR FIRST 15 CM OF CUT	0.91	0.50
12	RPWE/2	WELD ROOF PANEL - EACH SET OF 6 ADDITIONAL PIN HOLES OR 30 CM	1.8	1.00
13	RRRP	REPLACE EACH ROOF CORNER REINFORCEMENT (PROTECTION) PLATE	15.68	1.50
14	RRSW	STRAIGHTEN AND WELD ROOF REINFORCEMENT (PROTECTION) PLATE	0.91	0.50
15	RWRP/1	REPLACE 600 CM BY 240 CM FLAT ROOR ASSEMBLY W/O BOWS	508.71	18.00
16	RWRP/2	RELACE 1200 CM X 240 CM FLAT ROOF ASSEMBLY W/O BOWS	1097.4	26.00
17	RPST/4	STRAIGHTEN ACCUMILATED DENTS 7200 SQ CM	26.97	4.00

ROOF ASSEMBLY (CORRUGATED)

1	RCST/6	STRAIGHTEN ACCUMILATED DENTS 28800 SQURE CM	44.95	0.50
2	RCPA/5	PATCH ROOF 14400 SQURE CM	50.57	2.50
3	RCRP/2	REPLACE 240 IN X 600 CM CORRUGATED ROOF ASSEMBLY	78.37	20.00
4	RCST/5	STRAIGHTEN ACCUMILATED DENTS 14400 SQURE CM	22.48	5.15
5	RCPA/3	PATCH ROOF PANEL 3600 SQURE CM	16.86	1.50
6	RCST/3	STRAIGHTEN ACCUMILATED DENTS 3600 SQURE CM	5.62	2.15

ROOF ASSEMBLY (CORRUGATED)

1	RCPA/2	PATCH ROOF PANEL 900 SQ CM (30*30 CM)	4.23	1.00

SNo	Code	Item	Mat	Hr
2	RCPA/1	PATCH ROOF PANEL 225 SQ CM (15*15 CM)	1.06	0.75
3	RCST/1	STRAIGHTEN ACCUMULATED DENTS 900 SQ CM (30*30CM)	1.45	0.50
4	RCST/2	STRAIGHTEN ACCUMULATED DENTS 1800 SQ CM (30*60 CM)	2.81	1.00
5	RCWE/2	WELD CORRUGATED ROOF PANEL 30 CM	1.8	1.00
6	RCPA/4	PATCH ROOF-7200sq CM	33.71	2.00
7	RCSW/1	STRAIGHTEN AND WELD CORRUGATED ROOF PANEL CUT 15 CM	0.91	0.50
8	RCSW/2	STRAIGHTEN AND WELD CORRUGATED ROOF PANEL 30 CM	1.8	1.00
9	RCWE/1	WELD CORRUGATED ROOF PANEL 15 CM	0.91	0.50

ROOF ASSEMBLY(FLAT)

1	RBRP	REPLACE 1 ROOF BOW	20.31	1.25

ROOOF ASSEMBLY (FLAT)

1	RBWE	WELD ROOF BOW TO TOP RAIL	0.91	0.25
2	RBST	STRAINGTEN ROOF BOW	0.91	0.50
3	RBRB	REPLACE 1 ROOF BOW	20.16	1.25
4	RARP/2	REPLACE 600X1200 CM FLAT ROOF ASSEMBLY INCLUDING BOWS	142.7	34.00
5	RARP/1	REPLACE 600X240 CM FLAT ROOF ASSEMBLY INCLUDING BOWS	713.4	20.00

SECTION DOOR FRAME

1	DFSE/5	SECTION DOOR FRAME 2400 (FULL LENGTH)	113.2	1.00
2	DFSE/4	SECTION DOOR FRAME 1200MM	56.6	1.00
3	DFSE/3	SECTION DOOR FRAME 900MM	42	1.00
4	DFSE/2	SECTION DOOR FRAME 600MM	28.3	1.00
5	DFSE/1	SETION DOOR FRAME 300MM	14.15	1.00

SIDE PANEL

1	MWBPP/3	WIRE BRUSH, PRIME AND PAINT 28800 SQURE CM	9.52	1.50
2	SPPA/5	PATCH-14,400 SQ CM	50.56	2.50
3	SPRP	REPLACE ONE SIDE PANEL 120 X240 CM	134.82	6.00

SNo	Code	Item	Mat	Hr
4	MWBPP/2	WIRE BRUSH, PRIME AND PAINT ENTIRE INTERIOR	95.23	24.00
5	MWBTP/1	WIRE BRUSH AND TOUCH PAINT ENTIRE INTERIOR	14.28	10.00
6	MWBTP/2	WIRE BRUSH AND TOUCH PAINT ENTIRE INTERIOR	28.57	20.00
7	SPPA/3	PATCH SIDE PANEL 3,600 SQ CM (60*60)	16.86	1.50
8	SPPA/4	PATCH SIDE PANEL 7,200 SQ CM	33.7	2.00
9	MWBPP/1	WIRE BRUSH, PRIME AND PAINT ENTIRE INTERIOR	47.61	16.00

SIDE PANEL.

1	DPST/2	STRAIGHTEN ACCUMULATED DENTS 1800 SQ CM (30*60 CM)	3.42	1.00

SIDE PANELS

1	MWBTP/3	WIRE BRUSH & TOUCH PAINT ENTIRE EXTERIOR	14.15	10.00
2	SPSW/1	STRAIGHTEN AND WELD SIDE PANLE CUT 15 CM	0.91	0.50
3	SPPA/2	PATCH SIDE PANEL 900 SQ CM (30*30)	4.22	1.00
4	SPPA/1	PATCH SIDE PANEL UPTO FIRST 225 SQ CM (15*15 CM)	1.06	0.75
5	SPST/1	STRAIGHTEN ACCUMULATED DENTS900 SQ CM (30830CM)	1.4	0.50
6	SPST/2	STRAIGHTEN ACCUMULATED DENTS 1800 SQ CM (30*60)	2.8	1.00
7	SPST/3	STRAIGHTEN ACCUMULATED DENTS 3600 SQ CM (60*60)	5.61	2.15
8	SPST/4	STRAIGHTEN ACCUMULATED DENTS 7200 SQ CM (60*60)	11.23	2.75
9	SPST/6	STRAIGHTEN ACCUMULATED DENTS 28800 SQ M (120*240CM)	44.94	0.50
10	SPWE/2	WELD SIDE PANEL PIN HOLES(12 PIN HOLES) OR FIRST 15 CM CUT	1.8	1.00
11	SPSW/2	STRAIGHTEN AND WELD SIDE PANLE CUT 30 CM	1.8	1.00
12	MWBPP/5	WIRE BRUSH,PRIME & PAINT ENTIRE EXTERIOR	94.33	24.00
13	MWBPP/4	WIRE BRUSH , PRIME & PAINT ENTIRE EXTERIOR	47.16	16.00
14	MWBTP/4	WIRE BRUSH & TOUCH PAINT ENTIRE EXTERIOR	28.3	20.00
15	SPWE/1	WELD SIDE PANEL PIN HOLES (6 PIN HOLES)	0.91	0.50
16	SPST/5	STRAIGHTEN ACCUMULATED DENTS 14400 SQ CM (120*120CM)	22.47	0.50

SIDE RAIL

1	BRWE/1	WELD BOTTOM SIDE RAIL FIRST 15 cm	3.13	0.50

SNo	Code	Item	Mat	Hr
SUBSTRUCTURE/UNDERSTRUCTURE				
1	D14	CROOS MEMBER MISSING/ DAMAGED	1.13	0.00
TARPAULIN				
1	TP	TARPAULIN TORN/PIN HOLES UPTO 15X15 CM-PATCH	0	0.50
TOP SIDE RAILS				
1	TRSE/1	SECTION TOP SIDE RAIL (FULL PROFILE) 30CM	9.97	1.50
2	TRST/1	STRAIGHTEN TOP SIDE 15 CM	0.85	0.50
3	TRST/2	STAIGHTEN TOP SIDE RAIL 30CM	1.71	0.75
4	TRSW/1	STRAIGHTEN AND WELD TOP SIDERAIL 15CM	3.41	0.50
5	TRSW/2	STARIGHTEN AND WELD TOP SIDE RAIL EACH ADDITIONAL 15CM	6.83	0.75
6	TRWE/1	WELD TOP SIDE RAIL 15CM	3.13	0.50
7	TRWE/2	WELD TOP SIDE RAIL EACH ADDITIONAL 15 CM	6.83	0.75
8	TGRP	REPLACE GUSSET (INTERIOR TOP SIDE RAIL) (EACH)	5.14	0.25
9	TGSW	STRAIGHTEN AND WELD GUSSET (INTERIOR TOP SIDE RAIL) (EACH)	0.91	0.15
10	TRSE/2	SECTION TOP SIDE RAIL EACH ADDITIONAL 60 CM	19.94	2.50
11	TRIF/1	INSERT TOP SIDE RAIL(PARTIAL PROFILE) FULL LENGTH 600CM	77.3	11.00
12	TRIF/2	INSERT TOP SIDE RAIL (PARTIAL PROFILE) FULL LENGTH 1200 CM	154.54	20.00
13	TRSE/4	SECTION TOP SIDE RAIL (EACH ADDITIONAL 240CM	79.77	8.50
14	TRIN/4	INSERT TOP SIDE RAIL (PARTIAL PROFILE) 240 CM	49.21	4.50
15	TRIN/1	INSERT TOP SIDE RAIL(PARTIAL PROFILE) UPTO FIRST 30 CM	6.04	1.00
16	TRSE/6	SECTION TOP SIDE RAIL (EACH ADDITIONAL 960 CM	319.08	32.50
17	TRSE/5	SECTION TOP SIDE RAIL (EACH ADDITIONAL 480 CM	159.54	16.50
18	TRSE/3	SECTION TOP SIDE RAIL (EACH ADDITIONAL 120 CM	39.88	4.50
19	TRRP/2	REPLACE 1200 CM TOP SIDE RAIL (FULL PROFILE)	251.16	28.00
20	TRRP/1	REPLACE 600 CM TOP SIDE RAIL (FULL PROFILE)	125.58	15.00
21	TRIN/6	INSERT TOP SIDE RAIL (PARTIAL PROFILE) 960 CM	196.87	15.50
22	TRIN/5	INSERT TOP SIDE RAIL (PARTIAL PROFILE) 480 CM	98.43	7.50

SNo	Code	Item	Mat	Hr
23	TRIN/2	INSERT TOP SIDE RAIL (PARTIAL PROFILE) 60 CM	12.3	1.25
24	TRIN/3	INSERT TOP SIDE RAIL (PARTIAL PROFILE) 120 CM	24.6	2.50

TUNNEL ASSEMBLY

1	TLIN/2	INSERT GOOSENECK TUNNEL LONGITUDINAL RAIL 60 CM	9.51	2.00
2	TLSW/1	STRAIGHTEN AND WELD GOOSENECK TUNNEL LONGITUDINAL RAIL 15 CM	0.91	0.75
3	TLSW/2	STRAIGHTEN AND WELD GOOSENECK TUNNEL LONGITUDINAL RAIL 30 CM	1.8	1.50
4	TLWE/2	WELD GOOSENECK TUNNEL LONGITUDINAL RAIL 30 CM	1.8	1.00
5	TLWE/1	WELD GOOSENECK TUNNEL RAIL 15 CM	0.91	0.50
6	TARP	REPLACE COMPLETE TUNNEL ASSEMBLY	293.38	16.00
7	TLIF	INSERT GOOSENECK TUNNEL LONGITUDINAL RAIL FULL LENGTH 315 CM	91.82	5.00
8	TPRP	REPLACE GOOSENECK TUNNEL TOP PLATE AND STIFTENERS	138.85	8.00
9	TPST	STRAIGHTEN GOOSENECK TOP PLATE STIFTENERS	0.91	0.50
10	TLIN/1	INSERT GOOSENECK TUNNEL LONGITUDINAL RAIL 30 CM	4.75	1.00

UNDERSTRUCTURE

1	CMIN/1	INSERT CROSSMEMBER UPTO FIRST 30CM	6.83	1.00
2	CMIN/2	INSERT CROSSMEMBER EACH ADDITIONAL 60CM	13.67	2.00

UNDERSTRUCTURE ASSEMBLY

1	CMST	STRAIGHTEN 1 CROSSMEMBER	0.91	0.75
2	COIN/2	INSERT OUTRIGGER 60 CM	15.94	2.00
3	COWE/2	WELD OUTRIGGER FLANGE 30 CM	1.82	0.50
4	COWE/1	WELD OUTRIGGER FLANGE 15 CM	0.91	0.25
5	COSW/2	STRAIGHTEN AND WELD OUTRIGGER 60 CM	1.82	0.50
6	COSW/1	STRAIGHTEN AND WELD OUTRIGGER FLANGE 15 CM	0.91	0.25
7	CFWE/2	WELD BOTTOM FLANGE CROSSMEMBER, OUTRIGGER, FORK POCKET 30 CM	1.82	0.50
8	CORP	REPLACE TUNNEL CROSSMEMBER (OUTRIGGER)	21.63	1.25
9	COIN/1	INSERT OUTRIGGER FIRST 30 CM	7.97	1.00
10	COIF	INSERT OUTRIGGER FULL LENGTH 75 CM	17.08	1.25

SNo	Code	Item	Mat	Hr
11	CMSW/2	STRAIGHTEN AND WELD CROSSMEMBER 30 CM	1.82	1.00
12	CMWE/2	WELD CROSSMEMBER 30 CM	1.82	0.50
13	COST	STRAIGHTEN TUNNEL CROSSMEMBER (OUTRIGGER)	0.91	0.50
14	CMWE/1	WELD CROSSMEMBER 15 CM	0.91	0.25
15	CMSW/1	STRAIGHTEN AND WELD CROSSMEMBER 15 CM	0.91	0.50
16	CFST	STRAIGHTEN BOTTOM FLANGE CROSSMEMBER, OUTRIGGER, FORK POCKET	0.91	0.25
17	CFSW/1	STRAIGHTEN AND WELD BOTTO FLANGE, CROSSMEMBER , OUTRIGGER FORK POCKET 15 CM	0.91	0.35
18	CFSW/2	STRAIGHTEN AND WELD BOTTO FLANGE, CROSSMEMBER , OUTRIGGER FORK POCKET 30 CM	1.8	0.70
19	CFWE/1	WELD BOTTOM FLANGE CROSSMEMBER, OUTRIGGER, FORK POCKET 15 CM	0.91	0.25
20	CMIF/1	INSERT FIRST CROSSMEMBER 240 CM (FULL LENGTH)	52.51	0.50

VENTILATORS

1	VPRM	REMOVE & REINSTALL PLASTIC VENT	0.91	0.50
2	VLAS/1	VENTILATOR LOOSE APPLY SEALANT	3.6	0.75
3	VIIN	INSERT INNER PANEL BEHIND VENT COVER (ONLY)	8.82	1.50
4	VLPA	PATCH STEEL INNER VENT (LARGE SIZE 60 X 10 CM)	17.65	0.75
5	VMRM	REMOVE AND REINSTALL MECHANICAL VENT	5.69	0.50
6	VMRP	REPLACE WELD-ON VENT WITH STEEL MECHANICALLY ATTACHED VENT	0.91	0.75
7	VPRP	REPLACE WELD-ON OR MECHANICALLY ATTACHED VENT WITH PLASTIC VENT	33.18	0.75
8	VSPA	PATCH STEEL INNER OR OUTER VENT (SMALL SIZE 10 X 10 CM)	3.13	0.25
9	VWRP	REPLACE WELD-ON VENT WITH WELD ON VENT	17.08	1.50
10	VCRP	VENTILATOR COMBINATION, INSERT INNER PANEL AND INSTALL PLASTIC VENT	10.24	2.25